



Pacific Insulation Products

"Tomorrow's Needs, Today's Products, Service Now"

Installed Insulation Systems Costs

Wall Systems

20' eave height/ \$50 per m/h burdened cost.

Compliant Systems for 2012 WSEC	Insulation Costs (SQFT)	26 Gauge Metal Wall System	Labor (SQFT)	Total Installed
"MBI + 2" Rigid (Exposed Rated Board)	2.25	1.25	2.25	5.75
Liner Systems (Double Layer)	1.50	1.25	1.60	4.35
Insulated Panel System (2.5")	5.00	0.00	0.62	5.62
"R-Seal" System (2.5")	2.48	1.25	0.50	4.23

Roof Systems

Compliant Systems for 2012 WSEC	Insulation Costs (SQFT)	24 Gauge Metal Roof System	Labor (SQFT)	Total Installed
Liner Systems (R-36 w/Thermal Block)	1.10	2.00	0.75	3.85
Insulated Panel System (4")	5.50	0.00	0.50	6.00
"R-Seal" System (2.5")	3.28	2.00	0.50	5.78

*** NOT INTENDED FOR ESTIMATING ***